Engineering Division W/OSO321:FJZ

NOAA WIND PROFILER MODIFICATION NOTE 6

(for Electronics Technicians)

SUBJECT : Installation, RF Gain Adjustment, and Sensitivity Time Control

(STC) Alignment of Type 2 Receivers.

PURPOSE : Replacement of the Type 1 receiver

EQUIPMENT AFFECTED: All 404 MHZ wind profilers.

SITES AFFECTED : See affectivity list on page 10 of this maintenance note.

PARTS REQUIRED : Type 2 Receiver with alignment tool.

MODIFICATION : Each station will receive the required parts. No technician action

PROCUREMENT required.

REQUIRED TOOLS AND : 5/16 in. open-end wrench
TEST EQUIPMENT #2 Phillips head screwdriver

Flat blade (3/16 in.) screwdriver Flat blade (1/8 in.) screwdriver 60-100 MHz Oscilloscope Alignment tool (tweeker) SMA (M) to BNC (F) adaptor 6 ft. RG-58 cable, BNC(M)-(M)

 50Ω load

TIME REQUIRED : 5 work hours, plus travel

EFFECT ON OTHER

INSTRUCTIONS

None. File this note in EHB-9

VERIFICATION : This modification was tested at the wind profiler site in

STATEMENT Platteville, CO.

GENERAL

This modification note contains instructions for the replacement of the Type 1 receiver for the 404 MHZ wind profiler system. Additionally, this modification note provides alignment procedures for the receiver gain adjustment and the STC circuit.



Power to the PA cabinet should always be turned off before any other equipment cabinet is powered down.

- 1. Locate the circuit breaker panel on the wall next to the GOES cabinet and power-down the profiler by turning **OFF** the circuit breakers in the following order:
 - a. Breaker 17/19 (Transmitter Cabinet)
 - b. Breaker 22 (Equipment Cabinet), and
 - c. Breaker 24 (Data Processor).
- 2. Remove the side panel from the beam steering unit (BSU) cabinet.
- 3. Disconnect the coaxial cables from connectors J2 (LO) and J4 (COHO) on the rear panel of the Type 1 receiver.
- 4. Disconnect the cables from connectors J5 (control) and J3 (output) on the rear panel of the Type 1 receiver.
- 5. Disconnect the coaxial cable from connector J1 (RF Input) on the rear panel of the Type 1 receiver.
- 6. Disconnect the power cable from connector J8 (*Power In*) on the rear panel of the Type 1 receiver.
- 7. Remove the four mounting screws from the front panel of the Type 1 receiver and slide the unit out the front of the BSU cabinet.
- B. Type 2 Receiver Installation Procedure
 - 1. Install the Type 2 receiver in the BSU cabinet and secure the four mounting screws on the front panel.
 - 2. Attach the adaptor cable (W27), supplied with the Type 2 receiver, to the power cable (cable previously connected to J6).
 - 3. Reconnect the interface cables to connectors J2, J3, J4, J5, and J8 on the rear panel of the receiver (Figure 1).




Figure 1 Type 2 Receiver Rear Panel

C. Receiver Noise Measurement Procedure

Use the profiler to measure the system noise level as a method of calibrating the receiver gain. A $50\,\Omega$ l load is used to terminate the input of the receiver (J1) to isolate it from any external noise sources. During this test, the profiler should be cycling normally in the operational mode. The profiler maintenance terminal (PMT) is used to display the value of the system noise.

- 1. Attach a 50 Ω terminator load to connector J1 (RF IN) on the rear panel of the receiver.
- 2. Power-up the profiler by turning **ON** the circuit breakers in the following order:
 - a. Breaker 24 (Data Processor)
 - b. Breaker 22 (Equipment Cabinet)
 - c. Breaker 19 (Transmitter Cabinet)



When the radar is powered up, it is somtimes necessary to reset the power amplifier RF driver (*Driver* Reset button on the AMP local monitor) to "Driver A". The RF driver can only be reset if the RF input LED on the AMP local monitor front panel is red (indicating the system is not transmitting). The driver can be reset immediately after turning ON the PA cabinet breaker (breaker #17 and #19).

3. Connect the PMT interface cable to the front panel of the status monitor, and power-up the PMT (laptop computer).

- 4. Once the PMT has logged onto the profiler system, allow the radar to go through one or two complete beam cycles as indicated by the BSU front panel LEDs. Beam cycles start and end in the east-high mode. As the radar completes one beam cycle, the front panel LED marked EAST will light.
- 5. Select *Display Current Output* from the PMT Main Menu. Select *Landline* from the menu. Select *Status Data* from the menu. The *System Status Data Block* screen will appear on the PMT (Figure 2).




Figure 2 Profiler Status Data Block Screen on the PMT

6. Locate the *System Noise* field on the PMT screen. This number should be 63 ±1 with J1 (RF IN) terminated. To assure repeatability of the system noise value, allow the radar to cycle through the beams several times. Press *F1* on the PMT each time the east beam is reached. Select *Status Data* again and check the System Noise.



If the system noise is 63 \pm 1, no adjustment is required. Proceed to the STC alignment procedure in Section E. If the system noise value is too high or too low, proceed to the receiver gain adjustment in Section D.

D. Receiver Gain Adjustment.

The receiver gain is changed by adjusting a potentiometer (pot) that is accessed by removing a port-screw, labeled *RF GAIN*, from the top panel of the receiver. The pot is a surface mount device and is very small (the screw in the pot is about the size of a pinhead). A special alignment tool is provided with the Type 2 receiver for adjusting these pots and should always be kept at the site.

- 1. Remove the blank panel above the receiver. This will allow easier access to the gain adjustment pot.
- 2. Remove the port-screw from the top of the receiver labeled RF GAIN and carefully insert the alignment tool in the hole as shown in Figure 3. Since the pot is not visible, it is necessary to rely on the "feel" to seat the alignment tool in the potentiometer screw head.




Figure 3 Receiver Gain Adjustment



Considerable care must be taken when making adjustments on this pot. Rotations of just a few degrees will cause significant changes to the receiver's gain.

- 3. Make small changes on the *RF GAIN* pot. Wait for the radar to cycle to the east beam and use the PMT to verify the system noise as described in Section 5. Repeat this process until the system noise value of 63 ±1 is obtained. Once this value is reached, verify consistency of the system noise value by checking several more continuous beam cycles.
- 4. Replace the *RF GAIN* port-screw on the receiver top panel.
- 5. Power-down the radar as described in Section A, step 1.
- 6. Remove the 50 Ω load from J1 (RF IN) and reconnect the coaxial cable between J1 on the receiver and the T/R switch.

E. STC Alignment Procedure

The STC circuit is used to attenuate atmospheric signal returns that can saturate the input amplifier of the receiver (in the three lowest range gates of the low mode). Receiver saturation causes a bias in the true atmospheric signal and can thus bias the wind measurements produced by the profiler.

The STC Alignment procedure requires an oscilloscope to monitor the waveform present at J6 (/n-phase) or J7 (Quadrature) on the rear panel of the receiver. Oscilloscope triggering is obtained from one of the T/R switch gating pulses. The alignment procedure is performed when the radar is cycling normally in operational mode during any of the three low modes.

- 1. Power-down the radar as described in section A, step 1.
- 2. Remove the four mounting screws from the front panel of the signal processor and pull the unit to its full out position. Remove the top cover panel from the signal processor.
- 3. Connect a probe to channel one of the oscilloscope. Unscrew the grabber-tip from the probe to expose the pointed tip. Locate J3 pin 2 inside the rear panel of the signal processor. Insert the scope probe into pin 2 of connector J3 as shown in Figure 4.
- 4. Screw an SMA to BNC adaptor onto connector J6 (/n-phase) or J7 (Quadrature) on the rear panel of the receiver. Connect a coax cable (with BNC connectors on both ends of the cable) between channel two of the oscilloscope and J6 (/n-phase) or J7 (Quadrature) output on the rear panel of the receiver
- 5. Oscilloscope Settings:

Time/Division = 5 μ Sec
Channel One:
Triggering on channel one = positive edge
Volts/Division = 2 (0.2 for XI0 probe)
Channel Two:
Volts/Division = 200 mV




Figure 4 Accessing the T/R Switch Trigger Pulse Inside the Signal Processor for the STC Alignment Procedure.

- **6.** Remove the two screws from the STC LVL (level) and STC DLT (delay) ports on top of the receiver. Refer to Figure 3.
- 7. Power-up the radar in the sequence as described in section C, step 2.
- 8. The oscilloscope will display waveforms similar to those shown in Figure 5. This figure shows the entire T/R pulse in reference to the receiver's video signal waveform. The STC circuitry is factory preset for * δ 8 μSec delay (measured from the falling edge of trace 1) and an attenuation level of 15 dB (* 300 mV p-p). These settings must be fine-tuned on a site-by-site basis to achieve the maximum benefit from the STC circuit.



If problems arise when fine tuning the level and delay settings of the STC circuitry, call the Profiler Control Center (PCC) for technical assistance at (303)497-6033.




Figure 5 Typical STC waveform on an oscilloscope. Top trace is the T/R switch gating signal. Bottom trace is the video signal present at J6 (I) or J7 (Q) output of the receiver.

9. Change the oscilloscope settings to 2 μ Sec/division, and trigger on the negative going edge of trace 1. This will provide greater resolution on the oscilloscope screen. Figure 6 shows the negative going edge of the T/R switch gating signal (top trace) and the effect of the STC circuit on the waveform (bottom trace). The STC is triggered on the negative edge of the T/R gating signal. The duration of the clamp is set by adjusting the STC DLT. The amplitude of the clamp is set by STC LVL.




Figure 6 Effects of changing the STC DLT and STC LVL. Top trace is the T/R Switch Gating Pulse. Bottom trace is the Video Signal present at J6 (I) or J7 (Q) output of the Receiver.



Care must be taken when making adjustments to the STC DLT and STC LVL pots. They are extremely delicate. Do not attempt to adjust these pots without an oscilloscope.

10. To adjust the STC Level, carefully insert the alignment tool into the STC LVL port on top of the receiver (see Figure 3).

Rotate **cw** to **increase** the level. Rotate **ccw** to **decrease** the level.

11. To adjust the STC Delay, carefully insert the alignment tool into the STC DLT port on top of the receiver (see Figure 3).

Rotate **cw** to **decrease** the delay Rotate **ccw** to **increase** the delay

- 12. Reinstall the two port screws removed from the STC DLT and STC LVL on top of the receiver.
- 13. Reinstall the blank panel above the receiver front panel, and reinstall the BSU cabinet side panel.

REPORTING MODIFICATION

Target date for reporting this modification is 30 days after receipt of this modification note and parts. Report completed modification on WS Form A-26, Maintenance Record, according to instructions in EHB-4, part 2, using reporting code PROF (Figure 7).

Acting Chief, Engineering Division

Attachment

SITES AFFECTED

HUDID	STATION ID	LOCATION					
ABQ	AZCN5	Aztec, N M					
AMA	TCUN5	Tucumcari,NM					
FWD	PATT2	Palestine,TX					
LUB	JTNT2	Jayton,TX					
MEG	OKLM6	Okolona, MS					
OUN	LMNO2	Lamont, OK					
OUN	PRCO2	Purcell, OK					
OUN	VCIO2	Vici, O K					
SHV	DQUA4	D e q u e e n , A R					
SHV	WNFL1	Winnfield, LA					
TSA	HKLO2	Morris(Haskell),OK					
ARX	BLRW3	BlueRiver, WI					
C Y S	MBWW4	MedicineBow,WY					
DDC	HVLK1	Haviland,KS					
DMX	SLA14	Slater,IA					
DNR	PLVC2	Platteville,CO					
EAX	LTHM7	Lathrop, MO					
GLD	RWDN1	McCook, NE					
ICT	HBRK1	Hillsboro,KS					
ICT	NDSK1	Neodesha, KS					
I L X	WNC12	Winchester, IL					
LBF	MRRN1	Merriman, NE					
MPX	WDLM5	Wood Lake,MN					
OAX	FBYN1	Fairbury, N E					
O A X	NLGN1	N e l i g h , N E					
PAH	BLMN7	Bloomfield,MO					
PUB	GDAC2	Granada,CO					
SGF	CNWM7	Conway,MO					
AETA2	HMRA2	Homer, AK					
VBGC1	VBGC1	Vandenberg AFB,CA					
WSMN5	WSMN5	White Sands Missile Range,NM					

WS HQ USE ONLY General			WS FORM A-26 (4/94) Supercolar WS Form 13-28, which are obscible ENGINEERING MANAGEMENT REPORTING SYSTEM MAINTENANCE RECORD													
					Time 0900	2. Initials FJZ		3. Response Priority (check one) O Immediate O Routine		one)	O Low Not Applicable		4. Close Date 05 /02 /			1100
5. Descripti		cemer	nt of the T	ype 1	receiv	er/										
Equipment Information		6. Station ID JTNT2	7. Equipment Gode PROF		R Serial Number 018				9. TM	10. AT M			40w Mal. 999			
OPE	IPMENT RATIONAL TUS TIMES	a. Fully	Operational	h. Logi	istics Delay	Parily Op	erational	· ·	∆ ii ⊖ther		d. Logastics Delay		Nat Operations)			05:30
				13. /	Parts	Fallur	e Info	rm a t	ion						14. Wor Inf	k Load ormation
Block #	k ASN		ь	b. NSN				c. TM	d. AT	e. How Mal.	g. Maint Hrs.		Type .	Staff Hrs.		
1															a Routine	
2															6 Non- routine	
3															c. Travel	03:00
4															d. Misc.	02:00
5															e. Overtime	
Miscellaneous Replaced receiver and adjusted in accordance with mod note 6 FJZ																
17 SPECIAL PURPOSE REPORTING 6 Mod. No.			- 1	Mod./Act./Deact 05/02/9					đ				c ·			
18. CONFIGURATION MGMT. REPORTING (use as directed)			Ь.	Manufacturer's Part No. of New Part							c. Revision No. of New Part					

Figure 7 A-26 Form

Issue Date Org.Code W/OSO32

NATIONAL WEATHER SERVICE Engineering Handbook

Program Part Section BHB-9 03 3.6

MODIFICATION NOTE INDEX M003 MICROCOMPUTER SYSTEM

Number	Date of Issue	Title
2	October 25, 1989	M003 Micro-ART Implementation
	November 27, 1989	Addendum to Modification Note 2 - Modem Switch Settings
3	June 15, 1990	SixPakPlus Multifunction Board Installation
4	December 14, 1995	SPU 11 Vaisala Sounding Processor Board Installation

MEMORANDUM FOR: All NWS Regional Headquarters, Regional Maintenance

Specialists, Electronic Systems Analysts, and Electronics Technicians [Engineering Handbook

(EHB)-9 distribution]

FROM: W/OPS1 + John McNulty

SUBJECT: Transmittal Memorandum for EHB-9 Issuance 01-05

1. Material Transmitted:

Engineering Handbook No. 9 (EHB-9), M003 Microcomputer System, Section 3.6, M003 Microcomputer System Modification Note 5, (for Electronics Technicians).

2. <u>Summary</u>:

 ${\tt M003}$ Microcomputer System Modification Note 5 provides 5.25 inch floppy drive installation instructions into a local office computer.

3. Effect on Other Instructions:

None.

Distribution:

